



NOTES:

BEMC ENGINEER MUST INSPECT PAD PRIOR TO THE POURING OF CONCRETE.

PAD MUST BE A MINIMUM OF 10' FROM THE BUILDING AND 14' FROM A DOOR OR WINDOW

POUR PAD USING 3000 LB. CONCRETE  
 3/8" REBAR TO BE PLACED AND TIED 3"  
 FROM PERIMETER AND WIRE MESHED  
 PAD TO BE 1 FOOT THICK AND EXTEND 6"  
 ABOVE FINAL GRADE

TITLE:		3-PHASE PAD DIMENSIONS	
75 KVA - 750 KVA		SCALE:	N.T.S.
DWN. BY: D. LITTLE	DATE: 8/27/07	SHEET 1 OF 1	
ENG. APPROV: B. SEALS	8/27/07	SIZE: A	